

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|------------|---------------------------|----------|
| 1. Public Land Survey | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| 2. Property Controlling in Section | S <u>7</u> | T <u>42N</u> R <u>28W</u> | <u>2</u> |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 18 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3		●											
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (2-Sec. 7) East 1/16 corner between Sections 6-7. Established in 1970 by A.O. Enger, RLS. Corner record dated 12/20/71. 1" ID x 36" iron pipe with 4" aluminum cap. "No trees or other objects nearby for witnesses". Enger notes: "Corner falls at approximate intersection of old fences going N, S. and E, indicating probable prior establishment".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(2-Sec. 7) Recovered the 1970 monument, as described, in good condition, at the intersection of old stone rows North and East. Left the monument in place and marked new witnesses as described below. The corner is being recorded in order to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2) Found 1" pipe with 4" alum. cap.

Blazed and scribed the following:


6" W. Spruce N53E 14.4' "1/16S BT"

5" W. Spruce S48E 17.2' do

6" W. Spruce S07W 8.7' do

4" W. Spruce N50W 8.8' do

Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 4/24/00

For the Michigan Department of Natural Resources - Forest Management Division