

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Dickinson	Located In:	Corner Code #
(County)		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ R ___ T 42N R 28W	I _____
	S ___ R ___ T 42N R 28W	A _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Apr 18 2000

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		●	5	4	3	2	1					
3			●										
4	7		8	9	10	11	12						
5													
6	18		17	16	15	14	13						
7													
8	19		20	21	22	23	24						
9													
10	30		29	28	27	26	25						
11													
12	31		32	33	34	35	36						
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (1-Sec. 8) West 1/16 corner between Sections 5 and 8. Established in 1970 by A.O. Enger, RLS. Corner record dated 12/21/71. 1" ID x 36" iron pipe with 4" aluminum cap. Cedar 7 N14W 41 links, Cedar 6 N48W 45 links.  
 (8-Sec. 5) West 1/16 corner of Section 5. Established in 1970 by A.O. Enger, RLS. Corner record dated 1/17/72. 1" ID x 36" iron pipe with 4" aluminum cap. Cedar 10 S42E 29.6', Cedar 8 N18:30W 2.1'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(1-Sec. 8) Recovered the 1970 monument as described, in good condition, and at record bearing and distance from the stump remains of the two 1970 cedar bearing trees. Made the monument firm and made new witnesses as described below. This corner is being recorded in order to update the accessories.  
 (8-Sec. 5) Recovered the 1970 monument as described, in good condition, and at record bearing and distance from the 1970 witness Cedar NW, found in good condition with scribing visible. The Cedar 8T SE, now a rotting stump, was also recovered at record bearing and distance. Left the monument in place and marked new witnesses as described below. This corner is being recorded in order to update the accessories.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(1) Found 1" pipe with 4" alum. cap. Blazed and scribed the following: 4" Balsam N49E 6.5'      "1/16S 8T" 6" Elm S45E 11.1'      do 5" Balsam S60W 6.3'      do 6" Balsam N67W 12.8'      do Bearings are magnetic. Distances are to notch in lower blaze.	(8) Found 1" pipe with 4" alum. cap. Blazed and scribed the following: 12" Cedar S13W 2.3'      "1/16S 8T" 18" Sugar West 17.8'      do 15" Cedar N32W 18.2'      do 8" Cedar N22W 2.2' The 1970 witness. Bearings are magnetic. Distances are to notch in lower blaze.
-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------



Signed by Stephan J. Szyszkoski Date 4/24/00  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division