

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson
 (County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---|---|-------|
| 1. Public Land Survey | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Nov 23 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

East 1/16 corner between Sections 4-9. Corner established and recorded in 1989 by D.B. Babbitt, RLS: "Set MPOL between the South 1/4 corner and the SE section corner of Section 4. DNR Monument. 4" Cedar S22W 11.9', 5" Cedar N67W 21.4', 5" Cedar N38E, 24.85', 4" Cedar S17E 29.25'."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the 1989 monument, a 1" ID iron pipe capped with a 4" dia. cast aluminum Michigan Dept. of Natural Resources tablet, appropriately stamped, in good condition, and at record bearing and distance from the 1989 accessories, all recovered in good condition. My measurements between this monument and the Section and 1/4 corners east and west show that this monument is 102.6' Westerly of the position intended in 1989. Analysis of the 1989 field notes does not result in an understanding of why this monument is located at this position. I conclude that the 1989 placement is erroneous. I removed the 1989 monument and placed it midway and on a line of mean true bearing between the Quarter corner 1327.75' West and Section corner 1327.75' East. I defaced the 1989 bearing trees and made new as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" pipe with 4" MDNR cap.
 Blazed and scribed the following:
 14" Cedar S41E 25.6' "1/16S BT"
 8" Cedar S19E 18.8' do
 7" Cedar S86W 0.6' do
 6" Cedar N58W 5.0' do
 Set squared cedar post adjacent.
 Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 5/9/00

For the Michigan Department of Natural Resources - Forest Management Division