

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Dickinson  
(County)

Located in: Corner Code #

- |                                    |   |             |
|------------------------------------|---|-------------|
| 1. Public Land Survey              | T <u>42N</u> R <u>28W</u>                 | <u>81</u>   |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
| 2. Property Controlling in Section | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
| 3. Miscellaneous Property in Sec.  | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 20 2000

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 (B1) North Quarter corner of Section 6. Corner reestablished in 1970 by A.O. Enger, RLS using proportionate methods. 1" ID x 36" iron pipe with 4" aluminum cap. Hemlock 14 S38W 14.5', Hemlock 10 West 8.6', Sugar Maple 6 N6E 3.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B1) Found the 1970 monument as described, in good condition, and at record bearing and distance from the 1970 NBTs. The Hemlocks are now stump remains. It appears that the distances to them were transposed on the 1970 record. The sugar maple is in good condition. Left the monument in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B1) Found 1" ID iron pipe with 4" aluminum cap. Blazed and scribed:  
 17" Y. Birch S40W 12.9' "1/4S NBT"  
 7" Sugar N44W 13.65' do  
 7" Sugar S47E 9.15' do  
 Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 5/2/01

For the Michigan Department of Natural Resources - Forest Management Division