

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson
 (County)

Located in:

Corner Code #

- | | | | | |
|------------------------------------|---|-------------|-------------|-------------|
| 1. Public Land Survey | T | <u>42NR</u> | <u>28W</u> | <u>K1</u> |
| | T | <u>42NR</u> | <u>28W</u> | <u>J1</u> |
| 2. Property Controlling in Section | T | <u> </u> | <u> </u> | <u> </u> |
| | T | <u> </u> | <u> </u> | <u> </u> |
| | T | <u> </u> | <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S | <u> </u> | <u> </u> | <u> </u> |
| | S | <u> </u> | <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S | <u> </u> | <u> </u> | <u> </u> |
| | S | <u> </u> | <u> </u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jul 20 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:


(K1) NE corner of Section 2. Corner perpetuated in 1989 by D.B.Babbitt, RLS at the position monumented in 1952. Brass Cons. Dept. Monument. 4" Spruce S85W 22.3', 7" Spruce N24E 23.3', 7" Spruce S55E 24.3', 9" Spruce N69W 24.3' (1952 NBT).
 (J1) N1/4 corner of Section 2. Corner reestablished in 1989 by D.B.Babbitt, RLS using proportionate methods. DNR monument. 9" B.Spruce N55W 26.35', 7" B.Spruce N22W 16.9', 8" B.Spruce N32E 19.7', 6" B.Spruce S33E 13.15'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K1) Recovered the 1952 monument, a 1" ID iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation tablet, in good condition and at record bearing and distance from the remains of the three 1989 NBT spruce trees, now all dead. The 1952 NBT spruce was recovered in good condition at record bearing and distance. Left the monument in place.
 (J1) Recovered the 1989 monument, a 1" ID iron pipe capped with a 4" dia. aluminum MDNR tablet, in good condition and at record bearing and distance from the 1989 witnesses, which, except for that NE, are all dead and down. Left the monument in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K1) Found 1" ID iron pipe with 4" brass cap. Blazed and scribed: 8" B.Spruce N49E 24.2' "S36 NBT" 12" B.Spruce N89E 19.3' do 8" Spruce S37W 31.7' "S2 NBT" 10" Spruce N69W 24.3' (1952 NBT) Bearings are magnetic. Distances are to notch in lower blaze.	(J1) Found 1" ID iron pipe with 4" aluminum cap. Blazed and scribed: 4" Balsam S70E 17.7' "1/4S NBT" 5" Balsam S63W 16.8' do 6" Balsam N83W 19.9' do 9" B.Spruce N32E 19.7' (1989 NBT) Bearings are magnetic. Distances are to notch in lower blaze.
---	---



Signed by Stephan J. Szyszkoski Date 5/2/01
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division