

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson

(County)

Located In: Corner Code #

1. Public Land Survey	T 42N R 28W	C9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 17 T 42N R 28W	4
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

4 May 19 2005
 C9 Apr 20 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration;
 (C9) Corner common to Sections 19-20-29-30. 1950: Established by John Burt - N6'W between Sections 29 & 30 ...80.00 Set Cedar post corner of Secs. 19-20-29-30. Y. Birch 16 S49E 40, Sugar 14 N59W 28. Found no subsequent record.
 (4-Sec. 17) Northwest 1/16 corner, Section 17. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C9) The original post and accessories were not recovered. Found a 1.5"ID x 6' long capped iron pipe stamped "T42N R28W 19-20-29-30", set firmly but bent over. The position of the pipe is N74W 9.1' from the double proportionate position using the original record between corners 1 mile in all four directions. My survey of Sec. 20 revealed physical evidence that Sec. 20 may have been at least partially surveyed many years ago, possibly by the Dickinson Co. Road Commission in 1915. Despite having no explicit record, I accept the pipe as the best available evidence of the position of the original corner. Replaced found pipe with a new monument.
 (4-Sec. 17) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. From the position thus established, I found a metal fence post S67W 8.9' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 6" Balsam N61E 48.3' mrkd "S20 NBT" 5" Balsam S14W 35.9' "S30 NBT" 6" Cherry N85W 8.5' "S19 NBT" 7" Aspen N02W 18.7' "S19 NBT" Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 7" Sugar N12W 31.0' mrkd "1/16S BT" 8" Sugar S63E 22.0' do 7" Sugar S03W 15.5' do 9" Sugar N45W 23.6' do Set sq'd Cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/20/05