

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>42N</u> R <u>28W</u>	<u>D8</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>17</u> T <u>42N</u> R <u>28W</u>	<u>9</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

9 Jun 13 2005
 D8 Jun 09 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (D8) Center of Section 20. Not established in the original survey. 1915 notes of Dickinson County Road Commission show that some survey work was performed in this section but the extent of that work is not clear.
 (9-Sec. 17) East 1/16 corner, Sec. 17. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D8) Found no monumentation at the corner position. Found an old fence line to north, along the N-S 1/4 line, and old fence to west along the E-W 1/4 line, as well as the center of an E-W road which services a private residence just west of D8 and runs east to Co. Rd. 581. The intersection of the fenceline extensions with the road centerline occurs at a position that is just 3.6' west and 3.8' south of the intersection of straight lines connecting opposite 1/4 corners. From this, and from the pattern of other improvements within this section, it appears that the section had been previously subdivided by approved methods. Consequently, I monument D8 in accordance with the physical evidence found and reestablish D8 at the intersection of the fence lines to the west and north, and in the center of the gravel road.
 (9-Sec. 17) Established the corner midway and on a straight line between Quarter corner 1326.59' East and Center of Section 1326.59' West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D8) Set 1"IDx32" I.pipe with 4" alum. cap driven to 6" below road surface.	(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
Set measuring nails in:	6" Hemlock N44E 28.5' mrkd "1/16S BT"
15" Spruce N47E 26.3' mrkd "C1/4 BT"	10" Maple S82E 25.6' do
10" Spruce N73E 53.0' do	7" Hemlock S63W 43.8' do
7" Apple S25E 35.4' do	6" Cedar N55W 32.3' do
Power pole 78-0034 S5W 29.4' nail/tag	Set sq'd cedar post adjacent. Bearings
Bearings are magnetic. Distances are to nail with tag.	are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/20/05