

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T ___ R ___
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section

S 20 T 42N R 28W 4
 S 20 T 42N R 28W 3

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 13 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(4-Sec. 20) Northwest 1/16 corner, Section 20. Not established in the original survey.
 (3-Sec. 20) North 1/16 corner between Sections 19 and 20. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(4-Sec. 20) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
 (3-Sec. 20) Established the corner midway and on line between Quarter corner 1324.20' south and Section corner 1324.20' north. The position for the corner falls at the south edge of a cleared field.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 8" B.Spruce N20E 21.6' mrkd "1/16S BT"
 5" B.Spruce S48E 25.8' do
 5" B.Spruce S12E 15.2' do
 10" B.Spruce S85W 3.4' do
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.

(3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 5" W.Birch S72E 23.7' mrkd "1/16S BT"
 10" Sugar S47E 14.7' do
 9" Balsam S25E 7.5' do
 11" Sugar S24W 24.7' do
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/20/05