

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

|                                       |                         |               |
|---------------------------------------|-------------------------|---------------|
| <u>Dickinson</u>                      | Located In:             | Corner Code # |
| (County)                              |                         |               |
| Felch Township                        |                         |               |
| 1. Public Land Survey                 | T 42N R 29W             | J05           |
|                                       | T 42N R 29W             | G05           |
|                                       | T _____ R _____         | _____         |
| 2. Property Controlling in Section    | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                         |               |
| 5. Private Claims                     |                         |               |

Register of Deeds Stamp & File Number

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Jeremy J. Pipp, in a field survey on 7/30/2012AD do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J05) Quarter corner common to Sections 11 and 14. 1849: John Burt, DS. Set Cedar post witnessed by Cedar 8 S36E 30 links (19.80'), Spruce 12 N65W 45 links (29.70').

(G05) Corner common to Sections 9, 10, 15, and 16. 1849: John Burt, DS. Yellow Birch 30 for corner.; 1977: Michigan DNR (Arthur Enger PS#13581) set DNR monument witnessed by: 7" Sugar Maple S13W 8.8', 7" Sugar Maple S38E 27.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J05) No evidence of original survey or subsequent restoration found. Corner position reestablished by single proportionate measurement between the Northwest corner and the Northeast corner of Section 14; position checks well with line call East ("38.00 Chains Top of Ridge 20 feet C.N.W.") and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

(G05) Accepted found MDNR Monument and two existing NBT Witnesses. Left MDNR monument in place and rewitnessed. Accepted found MDNR Monument and Witnesses as a careful and faithful REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

|            |                        |               |                       |
|------------|------------------------|---------------|-----------------------|
| (J05)      | DNR monument           | (G05)         | DNR monument          |
| 6" Ash     | N73E 6.21' (1/4S,NBT)  | 5" Maple      | N19E 17.68' (S10,NBT) |
| 6" Ash     | S03E 12.53' (1/4S,NBT) | EX. 9" Maple  | S28E 27.84' (S15,NBT) |
| 7" Tw. Ash | S55W 21.19' (1/4S,NBT) | EX. 10" Maple | S17W 9.00' (S16,NBT)  |
| 8" Ash     | N34W 10.00' (1/4S,NBT) | 5" Maple      | N29W 20.37' (S9,NBT)  |

All trees are blazed, scribed, painted, and signed. Measurements are to nail in side of tree, bearings are magnetic. A carsonite rail was set North 1.5 feet.

Signed by Jeremy J. Pipp Date August 28, 2012  
 Surveyor's Michigan License No. 50447

