

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

or corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
ELCH TOWNSHIP		
Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling Section	S <u>21</u> T <u>42N</u> R <u>29W</u>	<u>11</u>
	S <u>29</u> T <u>42N</u> R <u>29W</u>	<u>03</u>
	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

6/25/2014

Jeremy J. Pipp, in a field survey on 6/25/2014 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded in this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

(11) Southwest One-Sixteenth corner of Section 21. 2010: Applekamp Land Surveying (Steven Applekamp, PS#43045) Set Aluminum Capped rebar witnessed by Sugar 10 N77E 10.34', Sugar 9 S12E 20.00'.

(03) North One-Sixteenth corner common to Sections 29 and 30. Not set in original survey, no evidence of subsequent establishment.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(11) Accepted found Applekamp Monument and Two BT Witnesses (both living). Position is accepted as a careful and faithful PERPETUATION of the position of the original corner.

(03) Corner position established mid-point and on-line between the West One-Quarter corner and the Northwest corner of Section 29.

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) Applekamp monument
 EX 10" Maple N75E 10.34' (- , -)
 EX 9" Maple S13E 20.01' (- , -)
 8" Maple S60W 38.53' (1/16S,NBT)
 6" Maple N45W 16.39' (1/16S,NBT)

(03) DNR monument
 9" Ash N51E 17.24' (1/16S,BT)
 15" Cedar S69E 35.02' (1/16S,BT)
 7" Balsam S32W 18.30' (1/16S,BT)
 4" Ash N35W 8.65' (1/16S,BT)

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

Signed by Jeremy J. Pipp
 Surveyor's Michigan License No. 50447



Date: July 15, 2014

For the Michigan Department of Natural Resources Forest Resource Division