

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 14 PM 12:23

For corners in

Dickinson
(County)
Felch Twp.

Located in:

Corner Code #

1. Public Land Survey

T42NR 29W

B-11

T ___ R ___

C-11

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S ___

T ___ R ___

S ___

T ___ R ___

3. Miscellaneous
Property in Sec.

S ___

T ___ R ___

S ___

T ___ R ___

Register of Deeds Stamp & File Number

REGISTER OF DEEDS
DICKINSON COUNTY
MICHIGAN

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SECTION

I, Robert F. Perkins, in a field survey on Oct. 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11		●		●									
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-11 $\frac{1}{4}$ Corner Common to Sections 30
31
Post by John Burt, D.S. 1849
Original Bearing Trees
Cedar 8" N48°E 40 Lk.
Lynn 12" S70°W 33 Lk.

C-11 Southeast Corner Section 30
Post by John Burt, D.S. 1849
Original Bearing Trees
Sugar 22" S2°W 20 Lk.
Sugar 10" N33°E 21 Lk.

ACCEPTED BY THE DICKINSON COUNTY
CORNER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT
345 OF 1990 AT A MEETING HELD ON
12-7-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11 No Evidence of Original Corner
or its Accessories Found due to
heavy Mining activity in Area
(Groveland Mine).

C-11 No Evidence of Original Corner
or its Accessories Remain due to
Mining activity in Area. Found $1\frac{1}{2}$ " Sq.
Iron Bar flush with Ground and $1\frac{1}{2}$ "
Witness Pipe projecting 4' alongside.
Corner set from Mining Co. Coordinates
& accepted and used on numerous prior
Surveys.

R.F.P.
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 Determined Corner Location by Single
Proportionate Method between Section
Corners $\frac{1}{2}$ Mile East and West. Location
falls on side alope of Mine Rock Dump.
Set $3\frac{1}{2}$ " Stamped D.C. Remon. Witness
Corner 37.00' North on $\frac{1}{4}$ Line.
Witnesses to W.C.:
Balm 8" N85°E(M.B.) 8.50' Nail/Tag
Birch 3" N75°W(M.B.) 17.15' Centerline
Placed Carsonite Marker at W.C.
Birch 3" N26°E(M.B.) 14.72' Centerline

C-11 Accepted Iron Bar described in "B" above
as Best Available Evidence of Corner
Location. Replaced same with $2\frac{1}{2}$ " Stamped
D.C. Remon. Corner
New Witnesses:
Aspen 6" S76°E(M.B.) 24.75' Nail/Tag
Balm 4" N20°W(M.B.) 24.45' Nail/Tag
Balm 4" N45°W(M.B.) 38.60' Nail/Tag
Balm 10" S20°E(M.B.) 28.30' Nail/Tag
Placed Carsonite Marker 0.80' East

Signed by Robert F. Perkins
Surveyor's Michigan License No. 12027

Date Nov. 6, 1998

002-386