

RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 14 PM 12: 23

For corners in

<u>Dickinson</u> (County)	Located in:	Corner Code #
<u>Felch Twp.</u>	<u>T42NR 29W</u>	<u>C-10</u>
1. Public Land Survey	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

REGISTER OF DEEDS
DICKINSON COUNTY
CORNER RECORDATION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SECTION

I, Robert F. Perkins, in a field survey on Oct. 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-10 $\frac{1}{4}$ Corner Common to Sections 30/29
Set Cedar Quarter Post
John Burt, D.S. 1849
Original Bearing Trees
Cedar 22" S70°W 20 Lk.
Cedar 14" N59°E 17 Lk.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON
12-7-98


R.F.P.
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10 Found Sharpened Point of 2" Cedar Stake in Swamp Muck. Point Found is 12.1 feet North and 1.5 feet West of Mid-Point Position between Section Corner $\frac{1}{2}$ Mile North and $\frac{1}{2}$ Mile South and Agrees with G.L.O. Call to Swamp Edge. It is entirely possible that this is the Point of Burt's Original Corner Stake.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10 Accepted Post Point described above as Best Available Evidence of Corner Location. Placed 2 $\frac{1}{2}$ " Stamped D.C. Remon. Corner alongside Found Point in Place.
New Witnesses:
Cedar 8" N28°E(M.B.) 15.60' Nail/Tag
Cedar 12" S88°W(M.B.) 24.10' Nail/Tag
Tamarack 5" N61°W(M.B.) 12.93' Nail/Tag
Tamarack 10" S02°W(M.B.) 13.62' Nail/Tag
Placed Carsonite Marker 1.0' East



Signed by Robert F. Perkins
Surveyor's Michigan License No. 12027

Date Nov. 6, 1998

002 PAGE 388