

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 14 PM 12: 23

For corners in

<u>Dickinson</u>	Located In:	Corner Code #
(County)		
<u>Felch Twp.</u>		
1. Public Land Survey	T <u>42N</u> R <u>29W</u>	<u>B-11</u>
	T ___ R ___	<u>C-11</u>
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

REGISTER OF DEEDS
 DICKINSON COUNTY
 ROOM 1015 1000 W. WASHINGTON

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ **SECTION**
 5. Private Claims _____

I, Robert F. Perkins, in a field survey on Oct. 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11	●	●										
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-11 ³⁰ Corner Common to Sections 31
 Post by John Burt, D.S. 1849
 Original Bearing Trees
 Cedar 8" N48°E 40 Lk.
 Lynn 12" S70°W 33 Lk.

C-11 Southeast Corner Section 30
 Post by John Burt, D.S. 1849
 Original Bearing Trees
 Sugar 22" S2°W 20 Lk.
 Sugar 10" N33°E 21 Lk.

ACCEPTED BY THE DICKINSON COUNTY SURVEYOR GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-7-98

R.F.P.

COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11 No Evidence of Original Corner or its Accessories Found due to heavy Mining activity in Area (Groveland Mine).

C-11 No Evidence of Original Corner or its Accessories Remain due to Mining activity in Area. Found 1½" Sq. Iron Bar flush with Ground and 1½" Witness Pipe projecting 4' alongside. Corner set from Mining Co. Coordinates & accepted and used on numerous prior Surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 Determined Corner Location by Single Proportionate Method between Section Corners ½ Mile East and West. Location falls on side alope of Mine Rock Dump. Set 3½" Stamped D.C. Remon. Witness Corner 37.00' North on ½ Line.
 Witnesses to W.C.:
 Balm 8" N85°E(M.B.) 8.50' Nail/Tag
 Birch 3" N75°W(M.B.) 17.15' Centerline
 Placed Carsonite Marker at W.C.
 Birch 3" N26°E(M.B.) 14.72' Centerline

C-11 Accepted Iron Bar described in "B" above as Best Available Evidence of Corner Location. Replaced same with 2½" Stamped D.C. Remon. Corner
 New Witnesses:
 Aspen 6" S76°E(M.B.) 24.75' Nail/Tag
 Balm 4" N20°W(M.B.) 24.45' Nail/Tag
 Balm 4" N45°W(M.B.) 38.60' Nail/Tag
 Balm 10" S20°E(M.B.) 28.30' Nail/Tag
 Placed Carsonite Marker 0.80' East
 Date Nov. 6, 1998

Signed by Robert F. Perkins
 Surveyor's Michigan License No. 12027

002-386