

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>9</u>	T. <u>42</u> N. S., R. <u>29</u> E. W.	#10 & #15
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 10 (South 1/16 corner between Sections 8 & 9, T42N, R29W and
Corner 15 (West 1/16 corner between Sections 9 & 16, T42N, R29W:

Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 10: Established 5/10/77 on line between 1/4 cor. 20.083 ch. N and calculated double proportionate Sec. Cor. 20.083 ch. S. (See corner record for Corners E-3 and E-4 for explanation of reasons for not using existing monument at Sec. Corner 8, 9, 16, & 17).

Corner 15: Established 5/11/77 on line between 1/4 cor. 20.153 ch. E and calculated double proportionate Sec. Cor. 20.153 ch. W. (See corner record for Corners E-3 and E-4 for explanation of reasons for not using existing monument at Sec. Cor. 8, 9, 16, & 17).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 10 N64°E (mag.) 33.8 ft. "1/16S, BT"
 W. Spruce 13 S54°E (mag.) 24.0 ft. "1/16S, BT"
 Declination 2°35' West

Corner 15: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 5 N 3°E (mag.) 7.6 ft. "1/16S, BT"
 Sugar Maple 6 S35°W (mag.) 22.7 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 30, 1978
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

