

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 42 <del>XX</del> N. R. 29 <del>XX</del> W.	E-6
2. PROPERTY CONTROLLING IN SECTION 16	, T. 42 <del>XX</del> N. R. 29 E. W.	3 & 10
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 10, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner E6 (1/4 corner between Sections 16 & 17, T42N, R29W):**  
 Elm post (Not found. No subsequent monuments found.)  
 Y. Birch 12 S44W 15 ( " " " " accessories " )  
 Elm 6 N34E 40 ( " " " " " " )

**Corner 3 (North 1/16 corner between Sections 16 & 17, T42N, R29W) and  
 Corner 10 (South 1/16 corner between Sections 16 & 17, T42N, R29W):**

Neither of these corners established in original survey nor subsequently apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner E6:** Restored on line between Sec. Cor. 40.179 ch. S and calculated double proportionate Sec. Cor. 40.176 ch. N. (See Corner Record for E-3 and E-4 for explanation of reason for not using existing monument at Sec. Cor. 8, 9, 16, & 17).  
**Corner 3:** Established on line between 1/4 cor. 20.088 ch. S and calculated double proportionate Sec. Cor. 20.088 ch. N. (Same explanation as E-6 for not using existing Sec. Cor. 8, 9, 16, & 17.) See map on Corner Record for Corner E-7.  
**Corner 10:** Established on line between Sec. Cor. 20.0895 ch. S and 1/4 cor. 20.0895 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Monuments for all three corners: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Witnesses for Corner E6: Sugar Maple 9 S49°E (mag.) 37.7 ft. "1/4S, NBT"  
 (Declination 0°35' West.) Elm 9 N52°W (mag.) 15.6 ft. "1/4S, NBT"  
 Witnesses for Corner 3: Sugar Maple 6 N21°E (mag.) 43.3 ft. "1/16S, BT"  
 (Declination 1°20' West) Red Maple 10 West (mag.) 6.7 ft. "1/16S, BT"  
 Witnesses for Corner 10: B. Spruce 5 S4°E (mag.) 30.8 ft. "1/16S, BT"  
 (Declination 2°05' West) B. Spruce 7 N32°W (mag.) 14.4 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY  
*Arthur O. Enger*  
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 13581