

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. S., R. 29 E. W.	D-7
2. PROPERTY CONTROLLING IN SECTION 17	T. 42 N. S., R. 29 E. W.	#16
3. MISCELLANEOUS PROPERTY IN SECTION	T. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner D7 (1/4 corner between Sections 17 & 20, T42N, R29W):**
 - Fir 6 for corner tree (Not found. No subsequent monuments or accessories)
 - No original witnesses (No subsequent accessories found.)
 - Corner 16 East 1/16 corner between Sections 17 & 20, T42N, R29W):**
 - Not established in original survey nor subsequently, apparently.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner D7:** On 5/6/77, restored corner as harmoniously as possible with the original U.S. survey notes and a subsequent survey purporting to establish the West 1/16 cor. bet. 17 & 20. As the latter reportedly dates to the 1930's, but with no record as to how established, it was honored so far as direction of the west half-mile of the sec. line is concerned; but the 1/4 corner was otherwise restored equidistant (40.124 chains) from the sec. corners on either side, although not on line between them. It bears S89°01.1'E (true) 40.124 ch. from 17, 18, 19, 20 and S89°44.2'W 40.124 ch. from 16, 17, 20, & 21. The west half-mile is thus divided into segments 19.987 ch. long in the W'ly part and 20.137 ch. long in the E'ly part.
 - Corner 16:** Established 5/9/77 on line between Sec. Cor. 20.062 ch. E and 1/4 cor. 20.062 ch. W.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner D7:** 1" I. D. x 36" iron pipe with 3 3/4" aluminum cap.
 - Red Maple 6 S51°E (mag.) 20.8 ft. "1/4S, NBT"
 - W. Spruce ? N43°E (mag.) 16.5 ft. "1/4S, NBT"
 - Declination is 4°15' West.
 - Corner 16:** 1" I. D. x 36" iron pipe with 3 3/4" aluminum cap.
 - Sugar Maple 10 N86°W (mag.) 21.3 ft. "1/16S, BT"
 - Sugar Maple 10 S74°E (mag.) 18.8 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 31, 1978

CHIEF OF SURVEY PARTY

 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

