

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. <u>9</u> , R. <u>29</u> <u>EX</u> W.	E-3 & E-4
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner E3 (Section Corner 4, 5, 8, & 9, T42N, R29W):**
 Hemlock post (Not found. Found 1" x 4" I. P. w/4" brass cap.)
 W. Pine 24 N53W 33 (Found. Found Aspen 5 S52E 12.5 lks. NBT.)
 W. Pine 24 S30E 11 (Found. " " 5 N47E 16.5 lks. NBT.)
- Corner E4 (1/4 corner between Sections 8 & 9, T42N, R29W):**
 Cedar post (Not found. See B for subsequent monument.)
 Cedar 12 N70W 9 (" " Found Su. Maple 5 N20W 13.5 lks. NBT.)
 Cedar 12 S44E 25 (" " " Spruce 6 S7°W 26.5 lks. NBT.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E3: On 6/23/76, rewitnessed corner as set by H. S. Peterson, RLS #8893 on 8/15/56, because his NBT's were in poor condition. Original W. Pine stumps still present.
Corner E4: Re-established 5/10/77 on line between Sec. Cor. 40.174 ch. N and double proportionate position of Sec. Cor. 40.174 ch. S. (The latter is not the position of the existing monument of record, which is located S65°08.5'E 36.96 ft. from the position calculated for the probable original location of the sec. cor., and which is more conformable to the notes and measurements of the original survey. In my opinion, the existing monument is erroneously set because insufficient information was available to the surveyor who placed it; but I have thought best not to disturb it as a large number of corners to the west were proportioned from it. However, I did think it proper

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: (to isolate the errors to those already made, and not extend them into my survey.) A monument described in C below, was placed previously at a point S52°06'E 23.10 ft. from the position described herein, but also erroneously, in my opinion.

- Corner E3:** 1" I.D. x 48" iron pipe with 4" brass cap (by H. S. Peterson)
 Sugar Maple 4 N88½°W (mag.) 22.1 ft. "S5, NBT"
 Red Maple 5 S30°E (mag.) 17.0 ft. "S9, NBT"
- Corner E4:** 1" I.D. x 36" iron pipe with 4" brass cap
 W. Spruce 11 S24°E (mag.) 36.0 ft. "1/4S, NBT"
 Sugar Maple 6 S36°W (mag.) 11.3 ft. "1/4S, NBT"
 Red Maple 8 N55°E (mag.) 9.6 ft. "1/4S, NBT"
 All others obliterated.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE December 1, 1977

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

