

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|--|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>42</u> N. <u>29</u> E. <u>W.</u> | E-7 |
| 2. PROPERTY CONTROLL- 16 ING IN SECTION _____ | T. <u>42</u> N. <u>29</u> E. <u>W.</u> | 15 |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. _____ E. _____ S. _____ R. _____ W. _____ | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E7 (Section Corner 16, 17, 20, & 21, T42N, R29W):
 Sugar post (Not found. No subsequent monuments found.)
 Hemlock 12 S52W 13 (" " " " accessories ")
 Sugar 16 N75E 24 (" " " " " ")

Corner 15 (West 1/16 corner between Sections 16 & 21, T42N, R29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E7: Re-established 4/19/77 by double proportionate measurement from corners 80.344 ch. S, 80.255 ch. E, 80.255 ch. W, and 160.688 ch. N. The position as thus set is in close agreement with record calls to natural features such as swamp edges, ridge tops, and streams to the N and S of it. Found a 14" cedar with blazes on 4 sides S79°E 44.9 ft. apparently marked for the approximate corner.
Corner 15: Established 4/20/77 on line between Sec. Cor. 20.064 ch. W and 1/4 cor. 20.064 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 5 N69°W (mag.) 19.5 ft. "S17, NBT"
 Sugar Maple 6 S78°E (mag.) 20.1 ft. "S21, NBT"
 Sugar Maple 6 S69°W (mag.) 13.6 ft. "S20, NBT"
Corner 15: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 7 S 8°W (mag.) 22.1 ft. "1/16S, BT"
 Red Maple 8 S32 E (mag.) 47.9 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE December 1, 1977

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

