

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. R. <u>29</u> E. W.	G-9
2. PROPERTY CONTROLLING IN SECTION <u>27</u>	, T. <u>42</u> N. R. <u>29</u> E. W.	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner G9 (Section Corner 21, 22, 27, & 28, T42N, R29W):  
 Cedar post (Not found. No subsequent monument found.)  
 Y. Birch 10 S35E 30 ( " " " " accessories " )  
 Cedar 12 N37W 29 ( " " " " " " )

Corner 3 (North 1/16 corner between Sections 27 & 28, T42N, R29W):  
 Not established in original survey and by approximation only, subsequently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner G9: Re-established 5/6/77 proportionately on line between original 1/4 cor. 39.944 ch. W and original 1/4 cor. 40.250 ch. E and 40.070 ch. S of an original 1/4 cor. to N. Proportion to the S was not used because of an apparent 1/2 chain error in the original survey measurement. Corner is 8.00 ch. S of a ledge top and 2 ch. E of a swamp edge and 20.09 ch. E of another swamp edge, almost exactly the record distances.  
Corner 3: Established 5/25/77 on line between Sec. Cor. 20.259 ch. N and 1/4 cor. 20.259 ch. S. Found a 3"x3"x5' squared cedar post S73°W 30.7 ft. for an approx. corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner G9: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Red Maple 8 N14°W (mag.) 26.8 ft. "S21, NBT"  
 Red Maple 8 S76°E (mag.) 51.4 ft. "S27, NBT"  
 Declination is 0°45' West.  
 Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Tamarack 7 S77°E (mag.) 49.2 ft. "1/16S, BT"  
 B. Spruce 4 S70°W (mag.) 40.1 ft. "1/16S, BT"  
 Declination is 1°15' West

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE December 1, 1977

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

