

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 29 E. W.	G-8
2. PROPERTY CONTROLLING IN SECTION	22, T. 42 N. R. 29 E. W.	10
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G8 (1/4 corner between Sections 21 & 22, T42N, R29W):

- Cedar post (Not found. See B for subsequent monument.)
- Y. Birch 12 N45W 8 (" " No subsequent accessories found.)
- Cedar 12 S49E 12 (Probably found. No subsequent accessories found.)

Corner 10 (South 1/16 corner between Sections 21 & 22, T42N, R29W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G8: On 6/2/76, placed a new monument at record bearing and distance from probable BT indicated above, located by reference to section corner distances on the reconstructed section line, and distances to streams N and S of this corner on the same reconstructed line. BT now a rotted stump fragment, identifiable only by species and relative size and position in relation to the proportionate 1/4 cor., which would fall S85°00'E 1.0 ft. from the corner set from the stump. Found a squared cedar post N73°20'E 26.4 ft., set by unknown persons for a temporary or approximate corner.

Corner 10: Established 5/6/77 on line between Sec. Cor. 20.035 ch. S and 1/4 cor. 20.035 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G8: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Cedar stump 22 S76½°E (mag.) 44.4 ft. "1/4S, NBT"
Cedar 16 N53½°E (mag.) 82.2 ft. "1/4S, NBT"
Declination is 3°00' West

Corner 10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
Sugar Maple 5 S86°W (mag.) 18.1 ft. "1/16S, BT"
Sugar Maple 8 N34°W (mag.) 34.5 ft. "1/16S, BT"
Distances horizontal. Declination 2°30' West. Also squared and scribed a 16" cedar 1.8 ft. S (to center of tree):

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE December 1, 1971

CHIEF OF SURVEY PARTY
Arthur O. Enger
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

