

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. <u>R.</u> R. <u>29</u> E. <u>W.</u>	G-7
2. PROPERTY CONTROLLING IN SECTION <u>22</u>	, T. <u>42</u> N. <u>R.</u> R. <u>29</u> E. <u>W.</u>	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner G7 (Section Corner 15, 16, 21, & 22, T42N, R29W):**  
 Cedar post (Not found. No subsequent monuments found.)  
 Y. Birch 10 S55E 18 (" " " " accessories " )  
 Cedar 14 N12W 63 (Probably found. No subsequent accessories found.)

**Corner 3 (North 1/16 corner between Sections 21 & 22, T42N, R29W):**  
 Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner G7:** On 6/2/76, replaced monument at record bearing and distance from BT indicated above, deduced as probably being such by measuring from an original corner 1½ miles N, another original corner 1½ miles W, and distances to 2 stream crossings to the S and one to the W. Subsequent measurements to corners S and E confirm the location as probable. The BT is a rotted stump of proper species and relative size, but has no marks.  
**Corner 3:** Established 5/6/77 on line between 1/4 cor. 20.033 ch. S and Sec. Cor. 20.033 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner G7:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Red Maple 7 N70°E (mag.) 46.5 ft. "S15, NBT"  
 Elm 22 N32°W (mag.) 4.3 ft. "S16, NBT"

**Corner 3:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Balsam 5 S76°W (mag.) 45.2 ft. "1/16S, BT"  
 Cedar 8 N48°W (mag.) 47.3 ft. "1/16S, BT"

Declination is 4°45' West

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE December 1, 1976  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources  
 13581

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

