

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>42</u> N. <u>31</u> S. R. <u>29</u> E. <u>W.</u>	H-9
2. PROPERTY CONTROLL- 22 ING IN SECTION_____	T. <u>42</u> N. <u>31</u> S. R. <u>29</u> E. <u>W.</u>	15
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. _____ S. R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner H9 (1/4 corner between Sections 22 & 27, T42N, R29W):

- Hemlock post (Not found. No subsequent monuments found.)
- Hemlock 22 N44E 31 (Probably found. No subsequent accessories found.)
- Hemlock 12 S56W 49 (" " " " " ")

Corner 15 (West 1/16 corner between Sections 22 & 27, T42N, R29W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner H9: on 6/4/76 re-monumented corner from probable remains of original BT's indicated above, identified by determining proportionate position of corner in relation to original 1/4 cor. 1 mile W and original sec. cor. 1/2 mile E, said point being N73°48'W 6.0 ft. from corner as found. BT's are badly rotted with no marks, but agree in species, relative size, and bearing and distance from corner. Corner falls on N side of rock ledge as in original notes.

Corner 15: Established 5/9/77 on line between Sec. Cor. 20.125 ch. W and 1/4 cor. 20.125 ch. E. (See map on corner record for Sec. Cor. 22, 23, 26, & 27.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H9: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap, set in mound of rocks.
Twin Sugar Maple 6 N4°E (mag.) 2.2 ft. "1/4S, NBT"
Sugar Maple 7 S78°W (mag.) 16.7 ft. "1/4S, NBT"

Corner 15: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Sugar Maple 4 S79°W (mag.) 4.2 ft. "1/16S, BT"
Sugar Maple 5 N80°E (mag.) 20.3 ft. "1/16S, BT"

Declination is 2°00' West

Note: Due to inadvertent displacement of the survey control, this monument may not be any more accurately placed than within a foot of where intended.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE Decemb. 1, 1979
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

