

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> ^{N.} 38 R. <u>29</u> ^{W.} W.	E-8
2. PROPERTY CONTROLL- 21 ING IN SECTION _____	T. <u>42</u> ^{N.} 38 R. <u>29</u> ^{W.} W.	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 20, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E8 (1/4 corner between Sections 20 & 21, T42N, R29W):

Cedar post (Not found. No subsequent monuments found.)
 Hemlock 14 N35E 27 (" " " " accessories ")
 Sugar 16 S27W 65 (" " " " " ")

Corner 3 (North 1/16 corner between Sections 20 & 21, T42N, R29W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E8: Re-established on line between Sec. Cor. 40.166 ch. to N and to S. Found a fence line going E about 13 ft. S of corner, apparently established at record distance N of Sec. Cor. to S, which distance appears not to have been the true distance. Corner appears to fall on an older fence line ridge to E, which is on the N edge of an old clearing line.

Corner 3: Established on line between 1/4 cor. 20.083 ch. S and Sec. Cor. 20.083 ch. N (See map on corner record for Sec. Cor. 21, 22, 27, & 28.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E8: 1" I.D. x 36" iron pipe with 3 3/4 aluminum cap.
 Sugar Maple 14 N38°14'W (true) 28.5 ft. "1/4S, NBT"
 Sugar Maple 6 N12°38'E (true) 16.6 ft. "1/4S, NBT"
 Declination is 12°00' West (apparently from local attraction)

Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 8 N43°E (mag.) 4.3 ft. "1/16S, BT"
 Basswood 6 N35°W (mag.) 1.9 ft. "1/16S, BT"
 Declination is 1°00' East.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE December 12, 1977

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

