

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

DICKINSON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 42 N. R. 29 E. W.	G-2
2. PROPERTY CONTROLLING IN SECTION _____	4 T. 42 N. R. 29 E. W.	7
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 24, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G2 (1/4 corner between Sections 3 & 4, T42N, R29W):
 Y. Birch post (Not found. No subsequent monuments found.)
 Cedar 10 N50W 17 (" " " " accessories ")
 Cedar 10 S18E 72 (" " " " " ")
Corner 7 (North 1/16 corner between Sections 3 & 4, T42N, R29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G2: Re-established proportionately on line between Sec. Cor. 40.025 ch. S and Sec. Cor. 40.836 ch. N. Position checks with original line tree stump 29.75 ch. S and a stream 9.31 ch. N.
Corner 7: Established proportionately on line between 1/4 cor. 20.013 ch. S and Sec. Cor. 20.823 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 6 S37°E (mag.) 20.0 ft. "1/4S, NBT"
 Red Maple 6 S30°W (mag.) 6.4 ft. "1/4S, NBT"
 Declination 3°15' East
Corner 7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 5 S67°W (mag.) 6.9 ft. "1/16S, BT"
 Sugar Maple 5 N72°E (mag.) 6.7 ft. "1/16S, BT"
 Declination 1°45' West

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 24, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

