

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>22</u>	T. <u>42</u> N. S., R. <u>29</u> <del>EX</del> W.	13 & 13a
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 9, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner 13 (Center of SE $\frac{1}{4}$  of Section 22, T42N, R29W):**

**Corner 13a (Aux. M.C. on East 1/16 line of Section 22, T42N, R29W):**

Neither of these corners established in original survey. It appears as if an attempt at establishment had been subsequently made, but there is no evidence to show that the prescribed method of sub-division was followed, and no monuments were found.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner 13:** Established at intersection of quarter-quarter section lines. (See map on corner record for Sec. Cor. 22, 23, 26, & 27.)

**Corner 13a:** Established on south shore of Six Mile Lake, N0<sup>o</sup>42.6'E 719.9 ft. from monument at Center of SE $\frac{1}{4}$  of Sec. 22. (See map on corner record for Sec. Cor. 22, 23, 26, & 27.)

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner 13:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap, set in a mound of rocks.  
 Sugar Maple 5 S51<sup>o</sup>E (mag.) 15.1 ft. "1/16S, BT"  
 Sugar Maple 8 S35<sup>o</sup>W (mag.) 8.8 ft. "1/16S, BT"

**Corner 13a:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Cedar 5 S38<sup>o</sup>W (mag.) 28.0 ft. "BT"  
 Cedar 5 S84<sup>o</sup>W (mag.) 33.3 ft. "BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE October 24, 1977

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

