

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

DICKINSON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. _____ E. _____ S., R. _____ W. _____		
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. _____ E. _____ S., R. _____ W. _____	22 42 N. 29 E.	12 & 12a
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ E. _____ S., R. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 13, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner 12 (South 1/16 corner on N & S 1/4 line of Section 22, T42N, R29W):  
 Corner 12a (Aux. M. C. on N & S 1/4 line of Section 22, T42N, R29W):  
 Neither of these corners was established in the original survey and there is no evidence that they were ever established subsequently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner 12: Established on N & S 1/4 line on line between South 1/4 cor. S0°12'45" W 1326.7 ft. and Center 1/4 cor. (in lake) N0°12'45"E 1326.5 ft. (See map on corner record for Sec. Cor. 22, 23, 26, & 27.)  
 Corner 12a: Established on true N & S 1/4 line on South shore of Six Mile Lake, N0°12'45"E 899.5 ft. from S 1/16 cor. and S0°12'45"W 427.0 ft. from calculated Center 1/4 cor. in lake. (See map on corner record for Sec. Cor. 22, 23, 26, & 27.)

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner 12: 4" dia. ⊕ chiselled in a rock ledge.  
 Sugar Maple 6 N74°W (mag.) 13.6 ft. "1/16S, BT"  
 Sugar Maple 4 N47°E (mag.) 27.6 ft. "1/16S, BT"  
 Corner 12a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Cedar stump 10 S30°W (mag.) 9.0 ft. "BT"  
 Cedar stump 8 S88°W (mag.) 10.4 ft. "BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE October 20, 1977  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

