

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. _____ N. _____ E. _____ S., R. _____ W.		
2. PROPERTY CONTROL- 22 _____ N. _____ ING IN SECTION _____ T. 42 _____ R. 29 _____ W.		8 & 8a
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ E. _____ S., R. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 13, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 8 (West 1/16 corner on E & W 1/4 line of Section 22, T42N, R29W):

Corner 8a (Aux. M.C. on E & W 1/4 line of Section 22, T42N, R29W):

Neither of these corners established in original survey. An attempt may have been made to establish them subsequently, although a 1" iron pipe found N86°58.7'E 359.4 ft. from Corner 8 can scarcely be construed to be the one-sixteenth corner. A similar pipe was found about 30-40 ft. NW'ly of Corner 8a. As neither of these monuments aligns with the true E & W 1/4 line, their validity can be discounted.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 8: Established on true E & W 1/4 line between West 1/4 corner S89°42.9'W 1333.1 ft. and Center 1/4 corner (in lake) N89°42.9'E 1333.1 ft. (See map on corner record for Sec. Cor. 22, 23, 26, & 27).

Corner 8a: Established on true E & W 1/4 line on West shore of Six Mile Lake, 836.3 ft. E'ly of West 1/16 cor. and 496.8 ft. W'ly of calculated Center 1/4 cor. in lake. (See map on corner record for Sec. Cor. 22, 23, 26, & 27).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 8: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Cedar 10 East (mag.) 6.5 ft. "1/16S, BT"
Cedar 15 S84°W (mag.) 19.3 ft. "1/16S, BT"

Corner 8a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
W. Spruce 20 S51°W (mag.) 30.8 ft. "AMC, BT"
Cherry 7 N54°W (mag.) 35.3 ft. "AMC, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 20,

CHIEF OF SURVEY PARTY
Arthur O. Enger
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

