

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. _____ N. S., R. _____ E. W. | _____ |
| 2. PROPERTY CONTROLLING IN SECTION _____ | 22, T. _____ 42 N. S., R. _____ 29 EX W. | 5 & 5a |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. S., R. _____ E. W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 4, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 5 (North 1/16 corner on N & S 1/4 line of Section 22, T42N, R29W):
 Not established in original survey. Found a 1" I.D. iron pipe alongside a 1/2" I.D. iron pipe N86°E (magnetic) 39.61 ft. and another 3/4" I.D. iron pipe (90°elbow screwed on top end) S59°E (magnetic) 22.26 ft., indicating attempts at establishment. Since most of the corners around Sec. 22 which control this corner were long since either lost or obliterated, any attempts at establishing it would appear to have been only by approximation.
Corner 5a (Aux. M.C. on N & S 1/4 line of Section 22, T42N, R29W):
 Not established in original survey and by approximation only, subsequently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 5: Established on true N & S 1/4 line between North 1/4 cor. N0°12'45"E 1327.7 ft. and Center 1/4 cor. (in lake) S0°12'45"W 1327.9 ft. (See map on corner record for Sec. Cor. 22, 23, 26, & 27.)
Corner 5a: Established on true N & S 1/4 line on North shore of Six Mile Lake, 348.8 ft. S'ly of N 1/16 cor. and 979.1 ft. N'ly of calculated Center 1/4 cor. in lake. (See map on corner record for Sec. Cor. 22, 23, 26, & 27.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Elm 8 S30°W (mag.) 6.9 ft. "1/16S, BT"
 Elm 5 N47°E (mag.) 8.5 ft. "1/16S, BT"
Corner 5a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 No witnesses readily available.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE October 20, 1977

MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

