

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

DICKINSON COUNTY

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. <u>X</u> , R. <u>29</u> W.	H-7 & I-7
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____, R. _____ E. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner H-7 (1/4 corner between Sections 15 & 22, T42N, R29W):

Cedar post	(Not found. See B for subsequent monument.)
Cedar 8 N57W 17	(" " No subsequent accessories found.)
Cedar 8 S12E 20	(" " " " " ")

Corner I-7 (Section Corner 14, 15, 22, & 23, T42N, R29W):

Cedar post	(Not found. Found 1" x 22" drill rod in place.)
Cedar 14 N60E 44	(" " No subsequent accessories found.)
Cedar 16 S58W 24	(" " " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner H7: Re-established 6/8/76 on line between Sec. Cor. S89°28.5'W 2673.9 ft. and Sec. Cor. N89°28.5'E 2673.9 ft. Found an old squared cedar post S74°35.4'E 107.9 ft. from corner reported herein, but could find nothing to support it as being original or even close to the original corner position. It bears S89°54.8'E 2777.8 ft. from NW sec. cor. and S88°48.8'W 2570.2 ft. from NE sec. cor., which seems highly unlikely based on other original corner evidence I found around the perimeter of Sec. 22. Corner as placed is reasonably conformable to original field note calls to swamp edge (very definite) 20.50 ch. (Record: 21.00 ch.) west and to another definite swamp edge 6.95 ch. (Record: 7:00 ch.) east.

Corner I7: On 4/28/76, replaced the drill rod with monument shown below. Rod has possibly been set by N. Thompson, a former local surveyor, from unknown evidence, but is more or less consistent with other corners around Sec. 22.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Cedar 18 S26°W (mag.) 54.2 ft. "1/4S, NBT"
 Cedar 14 S10°E (mag.) 47.2 ft. "1/4S, NBT"

Corner I7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 10 (E'ly of twins) N14°W (mag.) 33.3 ft. "S15, NBT"
 Sugar Maple 4 S60°W (mag.) 34.1 ft. "S22, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 20, 1971
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

