

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

DICKINSON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION _____	22, T. 42 N. S., R. 29 E. W.	14 & 14a
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 14 (South 1/16 corner between Sections 22 & 23, T42N, R29W):
Not established in original survey, and erroneously subsequently. Found a 1" I.D. iron pipe in a fence line S30°34'E 42.85 ft. from corner reported herein.

Corner 14a (South Meander Corner between Sections 22 & 23, T42N, R29W):
Not established in original survey, but may have been delineated subsequently, at least approximately.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 14: Established 4/22/76 on line between Sec. Cor. 1333.4 ft. S and computed 1/4 cor. (in lake) 1333.4 ft. N. (Refer to map on corner record for Sec. Cor. 22, 23, 26 & 27). There is no way that I can find the iron pipe referred to in A, above, to conform to the original survey notes for this section line.

Corner 14a: Established 4/28/76 on S shore of Six Mile Lake, N1°12.2'E 2197.1 ft. from Sec. Cor. to S and S1°12.2'W 863.7 ft. from calculated 1/4 cor. in lake. Position agrees with record distance to lake, but it is not known whether the lake edge is in the same place as at the time of the original survey. This procedure was adopted in order not to unsettle conditions in a number of adjoining M/B descriptions, which appear to have been established on the modern premise of where the

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 14: 1" I.D. x 36" iron pipe with 3 3/4 aluminum cap. (lake shore is.
Basswood 10 S86°W (mag.) 36.9 ft. "1/16S, BT"
Elm 10 N32°E (mag.) 27.4 ft. "1/16S, BT"
1" Iron Pipe S30°34'E 42.85 ft.

Corner 14a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Balm-of-Gilead 16 N56°E (mag.) 10.2 ft. "MC, BT"
Balm-of-Gilead 12 S 4°E (mag.) 5.5 ft. "MC, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 01, 1977

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

