

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION _____	T. <u>22</u> N. S., R. <u>29</u> E. W.	7 & 7a
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner 7 (North 1/16 corner between Sections 22 & 23, T42N, R29W):**  
 Not established in original survey; may have been established subsequently, but found no monuments.

**Corner 7a (North Meander Corner between Sections 22 & 23, T42N, R29W):**  
 Not established in original survey. Found a 1 1/4" well point N34°46'W 16.65 ft. indicating a recent attempt at establishment.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner 7:** Established 4/28/76 on line between Sec. Cor. N0°13.2'W 1333.4 ft. and calculated 1/4 cor. in lake S0°13.2'E 1333.4 ft. Corner falls in south ditch of an E & W road.

**Corner 7a:** Established 5/10/76 on N shore of Six Mile Lake, 2318.3 ft. S of Sec. Cor. to N and 348.5 ft. N of calculated 1/4 cor. in lake to S. The well point had probably been set by running a compass line South to the lake from a monument at the Sec. Cor. to N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner 7:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 B. Ash 7 S62°E (mag.) 6.0 ft. "1/16S, BT"  
 Cedar 6 S64°W (mag.) 34.1 ft. "1/16S, BT"  
 Top center of S. end of culvert N62°W (mag.) 1.90 ft.

**Corner 7a:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Elm 12 N57°E (mag.) 13.1 ft. "MC, BT"  
 1 1/4" Well point N34°46'W (true) 16.65 ft.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE October 19, 1977  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

