

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 42 ^{N.} 38 ³⁸ , R. 29 ^{W.} 38 ³⁸	#E-9
2. PROPERTY CONTROLLING IN SECTION 21 _____	T. 42 ^{N.} 38 ³⁸ , R. 29 ^{W.} 38 ³⁸	#10
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. ^{S.} , R. _____ ^{E.} W. ^{W.}	_____
4. LOT NO. _____	RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E9 (Section Corner 20, 21, 28, & 29, T42N, R29W):
 Cedar post (Possibly found. See B, below)
 Cedar 12 N64W 38 (Not found. No subsequent accessories found.)
 Cedar 10 S65E 19 (Not found. No subsequent accessories found.)

Corner 10 (South 1/16 corner between Sections 20 & 21, T42N, R29W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E9: On 5/4/77, replaced a 7/8"x24" length of re-inforcing rod found alongside the points of 5 old cedar posts submerged in the water incidental to its swamp location. It is very possible that one of the points is the original post. Several old blazes on nearby cedars, with indecipherable names and dates on some of them. Distances to swamp edges E and S check well with original field notes. As the position is not greatly at variance with other corners in the area, accepted it as probably the original corner position.

Corner 10: Established 4/20/77 on line between Sec. Cor. 20.083 ch. S and 1/4 corner 20.083 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E9: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Cedar 8 N48°W (mag.) 13.2 ft. "S20, NBT"
 Cedar 9 N33°E (mag.) 11.0 ft. "S21, NBT"
 Cedar 7 S74°W (mag.) 17.2 ft. "S29, NBT"

Corner 10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 7 N53°W (mag.) 23.1 ft. "1/16S, BT"
 Elm 12 S 1°E (mag.) 4.7 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE April 4, 1978

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

