

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 ^{N.} S. R. 29 ^{EX} W.	G-5
2. PROPERTY CONTROLLING IN SECTION	9, T. 42 ^{N.} S. R. 29 ^{EX} W.	14
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ ^{N.} S. R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 11, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G5 (Section Corner 9, 10, 15, & 16, T42N, R29W):
 Y. Birch 30 Corner tree (Not found. No subsequent monuments found.)
 No bearing trees (No subsequent accessories found.)

Corner 14 (South 1/16 corner between Sections 9 & 10, T42N, R29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G5: Restored proportionately on line between original Sec. Cor. 80.291 ch. S and an original hemlock line tree 7.527 ch. N.

Corner 14: Established on line between Sec. Cor. 20.093 ch. S and 1/4 cor. 20.093 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 7 S13°W (mag.) 8.8 ft. "S16, NBT"
 Sugar Maple 7 S38°E (mag.) 27.5 ft. "S15, NBT"
 Declination 2°35' West

Corner 14: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Cedar 14 N22°W (mag.) 12.8 ft. "1/16S, BT"
 Cedar 14 S41°W (mag.) 29.3 ft. "1/16S, BT"
 Declination 2°00' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 30, 1978
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

