

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>42</u> N. E. R. <u>29</u> E. W.	F-5
2. PROPERTY CONTROLLING IN SECTION <u>9</u>	, T. <u>42</u> N. E. R. <u>29</u> E. W.	16
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 11, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner F5 (1/4 corner between Sections 9 & 16, T42N, R29W):

Cedar post (Not found. No subsequent monuments found.)
 Cedar 14 N55E 35 (" " " " accessories ")
 Cedar 12 S59W 36 (" " " " " ")

Corner 16 (East 1/16 cor. between Sections 9 & 16, T42N, R29W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner F5: Restored in accordance with original field notes on line between Sec. Cor. 40.306 ch. E and calculated double-proportionate Sec. Cor. 40.306 ch. W. (See corner record for Corners E-3 and E-4 for explanation of reasons for not using existing monument at Sec. Cor. 8, 9, 16, & 17.) Found a cut-down cedar snag which had apparently been blazed to represent this corner, S86°E 24.0 ft. but could not identify any record BT evidence from it, so did not accept it.

Corner 16: Established on line between Sec. Cor. 20.153 ch. E and 1/4 cor. 20.153 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner F5: 1" I. D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 5 N 7°E (mag.) 14.1 ft. "1/4S, NBT"
 Sugar Maple 5 S52°E (mag.) 3.3 ft. "1/4S, NBT"
 Declination 0°55' West

Corner 16: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 6 N74°E (mag.) 15.4 ft. "1/16S, BT"
 Sugar Maple West (mag.) 10.7 ft. "1/16S, BT"
 Declination 2°10' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 30
CHIEF OF SURVEY PART
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

