

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. <del>38</del> R. 29 <del>38</del> W.	G-10 & G-11
2. PROPERTY CONTROLLING IN SECTION	.T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	.T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner G10 (1/4 corner between Sections 27 & 28, T42N, R29W):**  
 Cedar post (Not found. No subsequent monuments found.)  
 Y. Birch 10 S35E 30 ( " " " " accessories " )  
 Cedar 12 N37W 29 ( " " " " " " )

**Corner G11 (Section Corner 27, 28, 33, & 34, T42N, R29W):**  
 Sugar post (Not found. Found a length of 3/4" re-rod buried in ground.)  
 Y. Birch 16 N45E 36 ( " " No subsequent accessories found.)  
 Sugar 10 S44W 14 ( " " " " " " )

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner G10:** Corner restored on 5/25/77 on line between Sec. Cor. 40.013 ch. S and Sec. Cor. 40.518 ch. N. There is a surplus over record distance of .531 ch. in this sec. line, .031 ch. of which is considered a general index error and the rest probably an original chaining error in the north 1/2 mile. Corner thus set falls on N bank of an old stream bed, as in original field notes, and is 1 ch. S of a bottomland edge, also as in original notes. Present stream bed is about 50 links S of old stream bed.

**Corner G11:** On 5/23/77, witnessed a 3/4" re-inforcing rod of unknown length found buried about 1 foot underground at intersection of an old fence line E with approx. CL of county roads S and W. Origin of rod unknown, but appears to have been in place for a considerable length of time, and is presumed to be the section corner by common report.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner G10:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 W. Birch 24 N25°E (mag.) 64.6 ft. "1/4S, NBT"  
 No others near. Declination 1°35' West.

**Corner G11:** 3/4" iron re-inforcing rod of unknown length.  
 Sugar Maple 14 East (mag.) 47.3 ft. "NBT"  
 Sugar Maple 12 S35°W (mag.) 57.3 ft. "NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 30, 1978  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

