

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T42N R29W  
T. 43. NR 29W . . .

Dickinson

COUNTY

Section corner common to sections 33 and 34, T43N R29W and

DESCRIPTION OF CORNER sections 3 and 4 T42N R29W

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER Cedar 7" S 12 W 24 links

marked, T42N R29W S 4 NBT

Cedar 12" N 75 W 10 links

Marked, T43N R29W S 33 NBT

Distances measured from center of brass cap to notch.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

Corner was shown to me by Norman J. Karsten, assistant District Forester, Iron Mountain.

Corner was replaced from 4 original bearing trees. One cedar in excellent condition, scribe marks very plain on both faces. 1 cedar in fair condition, scribe marks plain. 1 cedar in fair condition, stump in place with scar tissue evident. 1 spruce stump in place in poor condition. No marks visible. Found old wood post in place, down.

Corner was found while cruising timber in this area.

Corner was placed on 22 October 1956 with Norman J. Karsten.

SURVEYORS SEAL

  
Henry S. Peterson

SIGNED \_\_\_\_\_  
REGISTERED LAND SURVEYOR

DATE 10/26/56