

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 NR. 28-29 W

----- Dickinson ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 1-12-6-7

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 24" W. Pine stump N 77° E 36 links

"S 6 NBT"

7" Balsam S 74° W 54 links

"S 12 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced section corner from two white pine stumps bearing S 54° W 41 links and N 27° E 48 links.

Found old axe marks on both stumps. Stumps burned badly.

Found traces of stake in soil.

Distance agrees well with ledge 2.00 chs. south and stream and line tree to north.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 8/16/57
REGISTERED LAND SURVEYOR