

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 N.R. 29 W


Dickinson COUNTY

DESCRIPTION OF CORNER Section Corner for Sections 5-6-7-8

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 10/14/65 with Klawiter, Hinds, Alatalo

WITNESSES TO CORNER..... 2" Aspen (S 6 NBT), N 69° W, 28 $\frac{1}{2}$ Hrs.



2" Aspen (S 5 NBT), N 76° E, 10 $\frac{1}{2}$ Hrs.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by double proportioned measurement between Section Corners 1 mile to North, East and West and 2 miles to South.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/15/1965
REGISTERED LAND SURVEYOR