

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 N.R. 29 W


Dickinson COUNTY

DESCRIPTION OF CORNER Section Corner for Sections 7-8-18-17

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 10/15/65

WITNESSES TO CORNER..... 4" H. Maple (S8 NBT), N 09° E, 08 1/2 lks.



4" H. Maple (S8 NBT), N 84° E, 28 lks.

4" H. Maple (S7 NBT), N 80° W, 21 lks.

AND
5" H. Maple (S17 NBT), S 01° E 34 lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was reestablished by double proportioned measurement between Section Corners 1 mile to North, South, East and West.

SURVEYOR'S SEAL

Frank J. Bray
SIGNED Frank J. Bray
REGISTERED LAND SURVEYOR

DATE 11/15/1965