

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 42-43N R 29W

DESCRIPTION OF CORNER Section Corner 1, 2, 35, and 36

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 28, 1967

WITNESSES TO CORNER..... 18" White Pine (S 35 NBT) N26°W 67.9'



23" White Pine (S 1 NBT) S18°E 72.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one probable B.T.; a W. Pine stump bearing S43°W 18 links; found several old blazes facing corner location. Distance South to top of hill checks well.

Corner placed with Charlie Carey, Soil Conservation Service.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE

3/21/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68