

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

| FOR CORNERS OF—: | LOCATED IN—: | CORNER CODE NUMBER |
|---|--------------|--------------------|
| 1. PUBLIC LAND SURVEY _____ T. _____ N. S., R. _____ E. W. | | |
| 2. PROPERTY CONTROLL- ING IN SECTION _____ 21 _____ T. _____ 42 N. S., R. _____ 29 E. W. | | 6 & 9 |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W. | | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 6, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 6 (Center of Northeast 1/4, Section 21, T42N, R29W) and

Corner 9 (East 1/16 corner on E & W 1/4 line, Section 21, T42N, R29W):
Not established in original survey and by approximation only, subsequently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 6: Established 20.032 ch. E'ly of N 1/16 cor. on N & S 1/4 line and 20.044 ch. N'ly of E 1/16 cor. on E & W 1/4 line, which is the calculated intersection of quarter-quarter section lines. Found a forester's approximate corner post S73°W 44.1 ft.

Corner 9: Established on line between E 1/4 cor. 20.0035 ch. E and Center 1/4 cor. 20.0035 ch. W. Found a forester's approximate corner post S45°E 22.7 ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 6: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
W. Spruce 9 S35°E (mag.) 30.7 ft. "1/16S, BT"
W. Spruce 9 S35°W (mag.) 65.2 ft. "1/16S, BT"
Declination 5°30' West.

Corner 9: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Sugar Maple 3 N58°W (mag.) 18.2 ft. "1/16S, BT"
W. Spruce 6 S1°E (mag.) 26.2 ft. "1/16S, BT"
Declination 3°00' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 10 1978

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

