

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	(DICKINSON COUNTY) LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ S., R. _____ E.	_____
2. PROPERTY CONTROL- <u>21</u> LING IN SECTION _____, T. <u>42</u>	N. _____ K., R. <u>29</u> W.	8 & 12
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____	N. _____ S., R. _____ E.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 8 (West 1/16 corner on E & W 1/4 line, Section 21, T42N, R29W) and
 Corner 12 (South 1/16 corner on N & S 1/4 line, Section 21, T42N, R29W):
 Not established in original survey and by approximation only, subsequently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 8: Established 6/6/78 on line between W 1/4 cor. 20.067 ch. W and Center 1/4 cor. 20.067 ch. E. Found a 3/4" I.D. iron pipe S71°W 49.1 ft. for an approximate corner.

Corner 12: Established 6/7/78 on line between S 1/4 corner 19.8815 ch. S and Center 1/4 corner 19.8815 ch. N. Found a forester's approximate corner post N85°W 37.5 ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 8: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 6 S27°E (mag.) 17.1 ft. "1/16S, BT"
 Sugar Maple 6 N89°E (mag.) 12.7 ft. "1/16S, BT"
 Declination 1°10' West.

Corner 12: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 6 N18°W (mag.) 17.5 ft. "1/16S, BT"
 Sugar Maple 5 N52°E (mag.) 7.3 ft. "1/16S, BT"
 Declination 2°05' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

