

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. <u>K</u> , R. <u>29</u> <u>K</u> W.	F-8
2. PROPERTY CONTROLLING IN SECTION <u>21</u>	, T. <u>42</u> N. <u>K</u> , R. <u>29</u> <u>K</u> W.	5
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 6, 1978, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner F8 (Center of Section 21, T42N, R29W): and**

**Corner 5 (North 1/16 corner on N & S 1/4 line, Section 21, T42N, R29W):**  
**Not established in original survey and by approximation only, subsequently.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner F8:** Established at intersection of quarter-section lines.  
 Found a foresters' approximate corner post S54°W 33.5 ft.

**Corner 5:** Established on line between N 1/4 corner 20.055 ch. N and Center 1/4 corner 20.055 ch. S. Found a forester's approximate corner post S48°W 43.2 ft.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner F8:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Sugar Maple 4 N53°E (mag.) 8.2 ft. "1/4S, BT"  
 Sugar Maple 6 N37°W (mag.) 14.9 ft. "1/4S, BT"  
 Sugar Maple 8 S67°W (mag.) 32.0 ft. "1/4S, BT"  
 Declination 1°40' West.

**Corner 5:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Cedar 14 S88°E (mag.) 6.7 ft. "1/16S, BT"  
 Cedar 9 West (mag.) 3.9 ft. "1/16S, BT"  
 Declination 5°55' East.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE August 10, 1978  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

