

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(DICKINSON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 41 N. R. 29 <del>X</del> W.	#C-13 & D-13
2. PROPERTY CONTROLLING IN SECTION 32 _____	T. 41 N. R. 29 <del>X</del> W.	#15
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**Corner C-13 (Sec. Cor. bet. Sections 31 & 32, T41N, R29W on 4th Corr. Line):**  
 Found a 1" I.D. x 48" iron pipe with 4" brass cap as set by B. D. Buckler, L. S. #8887 on 5-13-60 and witnessed by him with a Soft Maple 9 S30°E 13 lks. and an Aspen 8 N31°W 35 lks. **Corner D-13 (1/4 cor. on S side of Sec. 32, T41N, R29W on 4th Corr. Line):**  
 Found a 1" I.D. x 48" iron pipe with 4" brass cap (bent over, in a low rock mound) as set by B. D. Buckler on 5-31-60 and witnessed by him with a J. Pine 9 N49°E 60 lks. and an Aspen 5 N41°W 25 lks., both dead and down. **Corner 15 (West 1/16 cor. on S side of Sec. 32, T41N, R29W on 4th Corr. Line):** Not established in original survey and only by approximation subsequently, as there is a forester's post S51°W 8.0 ft. from monument reported herein.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**Corner C-13:** Re-witnessed corner on 8-27-79, Because Buckler's aspen NBT is nearly dead. Buckler's corner record is on file.

**Corner D-13:** On 8-28-79 replaced Buckler's monument with new monuments shown below, as the long pipe was too unstable to support with a reasonable mound of rocks. Corner falls on exposed bedrock.

**Corner 15:** Established 8-27-79 on 4th Correction line, proportionately on line between Std. Sec. Cor. 19.8675 ch. W and Std. 1/4 cor. 19.8675 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Corner C-13:** Monument and NBT's as set by Buckler. Declination 1° 35' West.  
 Red Maple 5 S86°W (mag.) 38.8 ft. "S2, NBT" (Enger)

**Corner D-13:** Chiselled in bedrock, with a 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap set over it in a mound of rocks.  
 Red Maple 8 S45°E (mag.) 25.2 ft. "1/4S, NBT"  
 Red Maple 5 N82°W (mag.) 8.0 ft. "1/4S, NBT"  
 Declination 3° 35' West.

**Corner 15:** 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap, set in rock mound.  
 Red Maple 6 N42°E (mag.) 41.7 ft. "1/16S, BT"  
 Cedar 9 N55°W (mag.) 26.8 ft. "1/16S, BT"  
 Declination 3° 20' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 4, 1980  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
 Arthur O. Enger

Michigan Department of Natural Resources  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

