

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(DICKINSON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 29 <input checked="" type="checkbox"/> W.	#A-13
2. PROPERTY CONTROLLING IN SECTION 31	T. 41 N. R. 29 <input checked="" type="checkbox"/> W.	#15 & 16
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. R. _____ E. <input type="checkbox"/> W. <input type="checkbox"/>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A-13 (Twp. Cor. bet. Sec. 31, T41N, R29W and Sec. 36, T41N, R30W, on 4th Correction Line):

Found a 1" I.D. x 48" iron pipe with 4" brass cap as set by B. D. Buckler, L. S. #8887 on 7-27-55 and witnessed by him with a W. Pine stump 22 S70E 85 lks.

Corner 15 (West 1/16 corner on S. side of Sec. 31, T41N, R29W) and

Corner 16 (East 1/16 corner on S. side of Sec. 31, T41N, R29W):

Neither of these 2 corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A-13: On 8-22-79 marked additional witnesses to the corner, as shown below.

Corner 15: Established 8-22-79 on 4th Correction Line, proportionately on line between Std. Twp. Cor. 21.9045 ch. W and Std. 1/4 cor. 19.913 ch. E. Corner falls near top of a 50-ft. high granite hill c. NNE & SSW, and is 3.715 ch. W'ly of closing sec. cor. bet. Sec. 2 & 3, T40N, R30W.

Corner 16: Established 8-23-79 on 4th Correction Line, proportionately on line bet. Std. 1/4 cor. 19.970 ch. W and Std. Sec. Cor. 19.970 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A-13: Monument as set by Buckler. Declination 3° 20' West.

Red Maple 5 N86-1/2°W (mag.) 10.2 ft. "S36, NBT"

Red Maple 7 S25-1/2°W (mag.) 41.3 ft. "S 3, NBT"

Red Maple 4 S82° E (mag.) 30.7 ft. "S 2, NBT"

Distances horizontal.

Corner 15: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

W. Birch 6 N89°E (mag.) 19.0 ft. "1/16S, BT"

R. Maple 5 N80°W (mag.) 7.1 ft. "1/16S, BT"

Distances horizontal. Declination 2° 50' West.

Corner 16: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

Red Maple 7 S87°E (mag.) 27.6 ft. "1/16S, BT"

W. Birch 6 N66°W (mag.) 10.1 ft. "1/16S, BT"

Distances horizontal.

Declination 1° 45' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 9 1980

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

