

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. <u>X</u> R. <u>29</u> W. <u>X</u>	<u>#E-13</u>
2. PROPERTY CONTROLLING IN SECTION <u>32&amp;33</u>	T. <u>41</u> N. <u>X</u> R. <u>29</u> W. <u>X</u>	<u>#32-16 &amp; 33-15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner E-13 (Sec. Cor. 32 & 33, T41N, R29W on 4th Corr. Line):**  
 Found a small rock mound (stones scattered) erected by B. D. Buckler, L. S. #8887 on 5-31-60 and witnessed by him with a Jack Pine 7 N70°W 27 lks. and a Red Pine 10 N41°E 91 lks.

**Corner 32-16 (East 1/16 cor. on S. side of Sec. 32, T41N, R29W) and  
 Corner 33-15 (West 1/16 cor. on S. side of Sec. 33, T41N, R29W):**  
 Neither of these 2 corners established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner E-13:** On 8-29-79 remonumented corner as shown below, from Buckler's NBT's. Buckler's original corner record as to corner restoration, is on file.  
**Corner 32-16:** Established 8-29-79 on 4th Correction Line proportionately on line between Std. 1/4 cor. 20.054 ch. W and Std. Sec. Cor. 20.054 ch. E.  
**Corner 33-15:** Established 8-23-79 on 4th Correction Line, proportionately on line bet. Std. Sec. Cor. 19.896 ch. W and Std. 1/4 cor. 19.896 ch. E.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner E-13:** ⊕ chiselled in bedrock, with a 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap set over it in a mound of rocks. Declination 3° 25' West.  
 J. Pine 9 (Buckler's) N72° W (mag.) 17.0 ft. "S32, NBT"  
 R. Pine 14 (Buckler's) N43-1/2°E (mag.) 60.0 ft. "S33, NBT"  
**Corner 32-16:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Red Maple 9 S74°W (mag.) 24.2 ft. "1/16S, BT"  
 Red Maple 6 S14°E (mag.) 26.4 ft. "1/16S, BT" Declination 3° 55' West.  
**Corner 33-15:** ⊕ chiselled in bedrock, with a 1" I.D. x 34" iron pipe with 3 3/4" aluminum cap set in a mound of rocks. Declination 2° 30' West.  
 Red Maple 6 S35°E (mag.) 24.8 ft. "1/16S, BT"  
 Red Maple 8 N11°E (mag.) 26.2 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 4, 1980

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

