

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson

(County)

Located In:

Corner Code #

- 1. Public Land Survey T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S 22 T 42R R 29W 1
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on May 05, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 22) North 1/16 corner between sections 22 and 23. Corner previously recorded in 1977 by Arthur O. Hager, RLS as follows: 1" I.D. iron pipe with 3 3/4" aluminum cap. Witnesses: B. Ash 7 S62W 6.0' "1/16S BT"; Cedar 6 S64W 34.1' "1/16S BT"; Top center of S. end of culvert S62W 1.90'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7-Sec. 22) Found monument as described above at record bearing and distance from the Cedar BT and the culvert. The B. Ash BT has been disturbed by earthwork. Marked two new bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Found 1" iron pipe with NDR cap. Blazed and scribed the following new bearing trees:
11" B. Ash S48W 10.4' "1/16S BT"
8" B. Ash S12W 26.0' "1/16S BT"



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 9-16-93