

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson

(County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 29M	J9
	T 42N R 29M	I9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on January 10, 1995, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12							
5													
6	15	16	17	18	19	20	21	22	23	24			
7													
8	19	20	21	22	23	24							
9													
10	29	30	31	32	33	34	35	36					
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J9) Quarter corner common to Sections 23-26. Original corner established in 1849 by John Burt as follows: "40.00 Set Hemlock qr. Sect. post. Y. Birch 9 S57W 62, Y. Birch 12 N52E 69". Found no subsequent record.
 (I9) Corner common to Sections 22-23-26-27. Corner re-monumented and filed in 1977 by A.O. Enger, RLS as follows: 1" I.D. x 36" iron pipe with 3.75" aluminum cap, set in a rock mound. Sugar Maple 7 S20E 2.8', Sugar Maple 9 N32W 22.6', Sugar Maple 9 S52W 35.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J9) Original post and accessories not recovered. Found no evidence of subsequent monumentation nor any evidence of the position of the original corner on the ground. The corner area consists of relatively young sugar maples. The area in general shows signs ancient fires. Reestablished the corner proportionate to the original record, on a straight line between adjacent section corners 2651.16' east and west. The line between 23-26 runs most of the way on the north side of a ledge of greenstone, as indicated by Burt.
 (I9) Found and accepted Enger's monument as described, in good condition, and at record bearing and distance from all three 1977 witnesses: 10" Sugar S16E 2.8', 12" Sugar N30W 22.6', and 10" Sugar S52W 35.8'. Left the monument in place and marked one new bearing tree as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J9) Placed a 1" ID x 24" iron pipe, driven into the rocky crevices on the north side of a ridge, capped with a yellow plastic cap "MICH DNR LS 33986". Blazed and scribed the following:
 9" Sugar S71W 28.8' "1/4S NBT"
 9" Sugar N55W 30.2' (slope) "1/4S NBT"
 5" Sugar N82E 25.5' "1/4S NBT"
 6" Sugar with location poster S23E 5.1' arkd "1/4S NBT". Bearings are magnetic.
 (I9) Found 1" iron pipe with aluminum MONR cap. Blazed and scribed the following new bearing tree:
 8" Sugar N70E 14.6' "S23 NBT" Magnetic bearing.



Signed by Stephan J. Szyszkoski Date 2-22-95
 Surveyor's Michigan License No. 33986