

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

1999 NOV 30 PM 3:21

For corners in

DICKINSON  
 (County)

Located In:

Corner Code #

SAGOLA TOWNSHIP

- |                                    |                             |             |
|------------------------------------|-----------------------------|-------------|
| 1. Public Land Survey              | T <u>42</u> N R <u>30</u> W | C-9         |
|                                    | T <u>42</u> N R <u>30</u> W | <u>C-10</u> |
|                                    | T _____ R _____             | _____       |
|                                    | T _____ R _____             | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____     | _____       |
|                                    | S _____ T _____ R _____     | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____     | _____       |
|                                    | S _____ T _____ R _____     | _____       |

REGISTER OF DEEDS  
 CLERK  
 STATE OF MICHIGAN

Register of Deeds Stamp & File Number

MAR 24 2000

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

SECTION

5. Private Claims \_\_\_\_\_

I, JAMES H. MOORE, in a field survey on AUGUST 16, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, reestablished, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-9 CORNER COMMON TO SECTIONS 19 - 20 - 29 - 30  
 CEDAR POST SET BY JOHN BURT D. S. 1849  
 CEDAR 12" S 44° W 35 LINKS  
 CEDAR 12" N 53° E 20 LINKS

C-10 ¼ CORNER COMMON TO SECTIONS 29 AND 30  
 SUGAR POST BY JOHN BURT D. S. 1849  
 SUGAR 8" S 55° W 18 LINKS  
 YELLOW BIRCH 14" N 42° E 35 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9 FOUND KIMBERLY-CLARKE CORP. 4" ALUMINUM CAP SPERHAKE, RLS 7876. DATE STAMPED 7-28-60.

C-10 FOUND KIMBERLY-CLARKE CORP. ALUMINUM CAP SPERHAKE, RLS 7876. DATE STAMPED 8-1-60.

1960 BEARING TREES  
 MAPLE 9" N 70° W 16 ½ LINKS  
 MAPLE 6" N 54° E 71 ½ LINKS  
 MAPLE 7" S 18° E 15 LINKS  
 MAPLE 7" S 56° N 30 ½ LINKS

1960 BEARING TREES  
 YELLOW BIRCH 14" N 20° W 62 LINKS  
 MAPLE 6" N 50° E 79 LINKS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 FOUND ABOVE MONUMENT IN PLACE NEW WITNESSES.


C-10 FOUND ABOVE MONUMENT IN PLACE NEW WITNESSES.

FOUND 12" MAPLE S 18° E (M.B.) 9.92' NAIL/TAG  
 FOUND 14" MAPLE N 65° W (M.B.) 10.60' NAIL/TAG  
 12" MAPLE S 72° W (M.B.) 19.98' NAIL/TAG  
 7" MAPLE N 46° E (M.B.) 10.88' NAIL/TAG  
 CARSONITE WITNESS POST S 40° W (M.B.) 1.10'

FOUND 15" YELLOW BIRCH N 16° W (M.B.) 40.65' NAIL/TAG  
 5" MAPLE N 68° W (M.B.) 42.91' NAIL/TAG  
 6" MAPLE S 29° W (M.B.) 38.95' NAIL/TAG  
 4" MAPLE N 60° E (M.B.) 31.95' NAIL/TAG  
 CARSONITE WITNESS POST N 50° E (M.B.) 1.00'

Signed by JAMES H. MOORE Surveyor's Michigan License No. 28423

Date 11-8-99



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 340 OF 1990 AT A MEETING HELD ON

REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT., 1995

*Liber B*

*PAGE 22*

*11-23-99*

*[Signature]*