

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1999 NOV 30 PM 3:21

For corners in

DICKINSON
(County)
SAGOLA TOWNSHIP

Located In:

Corner Code #

- | | | |
|------------------------------------|-----------------------------|-------|
| 1. Public Land Survey | T <u>42</u> N R <u>30</u> W | D-9 |
| | T <u>42</u> N R <u>30</u> W | E-9 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTERED
 DICKINSON COUNTY
 NOV 30 1999

Register of Deeds Stamp & File Number

SURVEY &
 RE-MONUMENTATION

4. Lot No. _____, Recorded Plat MAR 24 2000

5. Private Claims _____
 SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, JAMES H. MOORE, in a field survey on AUGUST 16, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| D-9 ¼ CORNER COMMON TO SECTIONS 20 – 29
CEDAR POST BY JOHN BURT, D.S. 1849
CEDAR 10" N 67° E 23 LINKS
CEDAR 14" S 25° W 10 LINKS | E-9 CORNER COMMON TO SECTIONS 20 – 21 – 28 - 29
CEDAR POST BY JOHN BURT, D.S. 1849
YELLOW BIRCH 6" S 16° E 18 LINKS
HEMLOCK 20" N 11° W 10 LINKS |
|---|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|--|---|
| D-9 FOUND KIMBERLY-CLARK CORP. 4" ALUMINUM CAP SPERHAKE, RLS 7876. DATE STAMPED 8-30-60.

1960 BEARING TREES
5" MAPLE N 28° W 34 ½ LINKS
7" MAPLE S 08° W 25 ½ LINKS | E-9 FOUND KIMBERLY-CLARKE CORP. 4" ALUMINUM CAP, SPERHAKE RLS 7876. DATE STAMPED 8-3-60.

1960 BEARING TREES
5" BLACK ASH N 70° W 54 LINKS
4" BLACK ASH N 40° E 23 ½ LINKS
5" SPRUCE S 66° E 55 LINKS
5" MAPLE S 42° W 39 LINKS |
|--|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| D-9 FOUND ABOVE DESCRIBED MONUMENT IN PLACE.
NEW WITNESSES

FOUND 16" MAPLE S 08° W (M.B.) 16.30' NAIL/TAG
FOUND 12" MAPLE N 28° W (M.B.) 22.75' NAIL/TAG
8" MAPLE N 45° E (M.B.) 10.09' NAIL/TAG
8" MAPLE S 76° E (M.B.) 17.14' NAIL/TAG
CARSONITE MARKER S 60° W (M.B.) 1.00' | E-9 FOUND ABOVE DESCRIBED MONUMENT IN PLACE.
NEW WITNESSES

7" ASH S 01° W (M.B.) 16.86' NAIL/TAG
7" ASH S 43° E (M.B.) 21.30' NAIL/TAG
8" SPRUCE N 07° E (M.B.) 14.30' NAIL/TAG
7" ASH N 77° E (M.B.) 7.18' NAIL/TAG
CARSONITE MARKER S 72° E (M.B.) 1.05' |
|--|--|

Signed by JAMES H. MOORE Date 11-8-99
 Surveyor's Michigan License No. 28423



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 346 OF 1990 AT A MEETING HELD ON MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995

Liber B PAGE 23

11-23-99
RBF